

SPECIFICATION			
HOISTING LOAD	3		TON
TESTING LOAD	3.75		TON
LIFT HEIGHT	5		M
PENDANT CABLE	4.5		M
HOISTING	SPEED	1.35 – 4.05	M/MIN
	MOTOR	3.5KW x 4P x 1SET	
TRAVERSING	SPEED	5.2 – 15.2	M/MIN
	MOTOR	0.75KW x 6P x 1SET	
POWER SUPPLY	AC 220/380,440,460,480x3øx60Hz		
OPERATING METHOD	P.B type ON . FL		
WEIGHT	535.0		KG
I-BEAM SIZE	125		MM
ADD. LOAD CHAIN	5.32		KG/M
ADD. PENDANT CABLE	0.28		KG/M

도면에 지시되지 않은 일반공차						
가공별	치수	3-6	6-30	30-120	120-315	315-1000
선	삭					
구멍간	거리	±0.1	±0.2	±0.3	±0.5	±0.8

REV.NO	DATE	REVISION DESCRIPTION	DRAWN	CHECKED	APPROVED
--------	------	----------------------	-------	---------	----------